



## SPU TRANSFORMER PAD SPECIFICATIONS

- The Customer shall install, own and maintain a concrete pad.
- A clear space of 10' must be left in front of the pad and transformer to provide working space for hotstick operation of the transformer.
- Two Customer-owned rigid conduits for primary to be installed at extreme LEFT edge of pad opening and extending at least 36" beyond areas that may become inaccessible. 4" duct minimum.
- One 2" rigid PVC installed on secondary side and extending at least 36" beyond areas that may become inaccessible.
- Customer-owned ducts for secondary cable to be installed at extreme RIGHT edge of opening.
- Pad dimension 7' x 6' x 6" reinforced with rod or wire mesh.
- Pad location to be approved by Utility.
- **Three customer-owned 2" rigid conduits to be installed from building to pad location for communication services. 24" separation between 2" ducts by pad**

